


MASTER



This is an informal report intended for use as a preliminary or working document

**GEND**

General Public Utilities • Electric Power Research Institute • U.S. Nuclear Regulatory Commission • U.S. Department of Energy

## **FIELD MEASUREMENTS AND INTERPRETATION OF TMI-2 INSTRUMENTATION: CF-1-PT3**

J. E. Jones  
J. G. Smith  
M. V. Mathis

Prepared for the  
U.S. Department of Energy  
Three Mile Island Operations Office  
Under DOE Contract No. DE-AC07-76ID01570

U.S. GOVERNMENT PRINTING OFFICE: 1981

## TABLE OF CONTENTS

| <u>Section</u>                                    | <u>Page</u> |
|---|-------------|
| 1. INTRODUCTION                                   | 1-1         |
| 2. INSTRUMENT LOCATION, CABLING, AND TERMINATIONS | 2-1         |
| 3. MEASUREMENT PROCEDURES                         | 3-1         |
| 4. MEASUREMENTS                                   | 4-1         |
| 5. INTERPRETATION OF MEASUREMENTS                 | 5-1         |
| 6. CONCLUSIONS                                    | 6-1         |
| APPENDIX  |             |

## LIST OF FIGURES

| <u>Figure</u>                                  | <u>Page</u> |
|--|-------------|
| 2-1 CF-1-PT4 Composite Electrical Diagram      | 2-2         |
| 2-2 Foxboro Model E11GM Design                 | 2-4         |
| 4-1 Current-to-Voltage Test Fixture            | 4-2         |
| 4-2 Oscilloscope Traces of Pressure Signal     | 4-3         |
| 4-3 Low Frequency Spectra of Pressure Signal   | 4-4         |
| 4-4 High Frequency Spectrum of Pressure Signal | 4-5         |
| 4-5 TDR Trace of Pressure Signal Lines         | 4-8         |
| 4-6 TDR Trace of (+) Signal to Shield          | 4-9         |
| 4-7 TDR Trace of (-) Signal to Shield          | 4-10        |

## LIST OF TABLES

| <u>Table</u>  | <u>Page</u> |
|---|-------------|
| 2-1 Termination Points for CF-1-PT4 Measurements        | 2-3         |
| 4-1 Capacitance, Impedance, and Resistance Measurements | 4-7         |
| 5-1 Major AC Components on the Pressure Signal          | 5-2         |
| 5-2 Summary of TDR Measurements                         | 5-4         |

## Section 1

### INTRODUCTION

During and following the TMI-2 accident, a number of instruments failed or were suspected of providing erroneous readings. Because of this problem, industry concerns were focused upon the behavior of instrumentation under adverse conditions. To better understand failure mechanisms, the Technical Integration Office (TIO) contracted Technology for Energy Corporation (TEC) to perform field measurements on a set of selected TMI-2 instruments to determine in-situ operating characteristics. For some instruments, these measurements were to be performed prior to removal (and replacement with new instruments) in order to have a cross reference with post-removal observations. For other instruments, an indication of the condition of the instrument (i.e., fully operational or failed) was desired.

This report describes the measurements and results on the Core Flood Tank 1B pressure monitor CF-1-PT4. This instrument consists of a Foxboro Model E11GM-HSAE1 electronic absolute pressure transmitter connected to a readout module by approximately 600 feet of cable through a penetration and an instrument mounting terminal block. This instrument was one of the few primary loop pressure monitors that was believed not failed during the accident. As a result, measurements on this instrument were performed to determine if it was properly functioning or if it had suffered some degradation.

## Section 2

### INSTRUMENT LOCATION, CABLING, AND TERMINATIONS

A review of appropriate drawings from Foxboro and Burns & Roe (itemized in the Appendix in the measurement procedure, pages A-5 and A-6) resulted in the composite electrical diagram shown in Figure 2-1. From this information, a list of the appropriate termination points for performing measurements in Control Cabinet 156 was generated and is given in Table 2-1. Figure 2-1 also indicates the cable lengths pulled during instrument installation and lengths after trimming between each termination and/or junction point.

The pressure sensing assembly is a Foxboro Model E11GM-HSAE1 which is shown in a cross-sectional view in Figure 2-2. This instrument has a normal range of 0-750 psia producing a 10-50 ma current output. The electrical diagram of the detector circuit is also shown in Figure 2-2.

Since measurements were being made in Control Cabinet 156, the effect of the readout meter (attached to the signal line) was also present on the observed instrument response. However, since this readout was located outside containment, it did not experience severe operating environments, and thus was not considered to have failed.




Figure 2-1. CF-1-PT4 Composite Electrical Diagram.

2-3


Table 2-1

TERMINATION POINTS FOR CF-1-PT4 MEASUREMENTS


| Signal  | Cabinet 156 Identification <sup>*</sup> |
|---------|---|
| +Signal | TB8-9-3/4                               |
| -Signal | TB8-9-3/5                               |
| Shield  | TB8-9-3/3                               |

<sup>\*</sup> From cable IT1722I





a. Cross Sectional View.



b. Electrical Schematic.

Figure 2-2. Foxboro Model E11GM Design.

### Section 3

#### MEASUREMENT PROCEDURES

As a result of generating the composite electrical diagram and from a review of the Foxboro E11A Series Electronic Absolute Pressure Transmitters technical information literature, measurements to be performed were identified as:

1. Determine as-found condition of pressure indication and record signal output.
2. Perform passive measurements (i.e., passively monitor signals) on each electrical connection consisting of time domain waveforms, very high frequency spectrum analysis (i.e., MHz region), and frequency spectra below 100 kHz.
3. Perform resistance, capacitance, impedance, and Time Domain Reflectometry (TDR) active measurements (i.e., actively introducing a test signal).

These measurements were designed to verify the operation of the Readout Module and the power supplies, but the focus of the measurement was on the pressure sensing assembly, cabling, and terminations/connections to the assembly. The Appendix contains the detailed procedure which was followed during the measurement program, and a summary of measurements is presented in the next section.


## Section 4

### MEASUREMENTS

Since the pressure signal from CF-1-PT4 was a 10-50 ma current loop, a test fixture was needed to convert this current to voltage for field measurements. A sketch of the test fixture used for this conversion is given in Figure 4-1. However, before insertion of the test fixture into the circuit, the readout of CF-1-PT4 was recorded as 170 psi to insure that the fixture did not affect the device. Following the test fixture insertion, the readout was 170 psi. Since there was no noticeable change in the readout, it was not believed that this load affected the instrument responses.

After the insertion of the test fixture and verification of CF-1-PT4 output reading, the 1-5 volt signal from the connections on the test fixture was recorded for approximately 10 minutes on a FM recorder. During this recording, the DC voltage was measured (with a Keithley Model 177 DVM) as 1.91 volts, or equivalently 19.1 ma current.

The next measurement consisted of photographing the output waveform from the screen of a storage oscilloscope. Figure 4-2 shows the results of these time trace measurements for two different time scales. Along with the time traces, both high and low frequency spectra (frequency domain) were taken of the signal. Figure 4-3 shows the measured spectrum over both a 6 MHz 400 kHz bandwidth, while Figure 4-4 shows spectra over both 100 kHz and 1 kHz ranges.



\*Note: 100 ohm resistance converts 10-50 ma range to 1-5 volts for testing.

Figure 4-1. Current-to-Voltage Test Fixture.



Photo 108-1

Time - 2msec/div

Gain - 50 mV/div





Photo 108-2

Time - 50 $\mu$ sec/div

Gain - 50 mV/div

Figure 4-2. Oscilloscope Traces of Pressure Signal.

-20db



Frequency (MHz)


Photo 108-3

BW - 3 KHz

Scan width - 1 MHz/div

Scan time - 1 sec/div

-20db



Frequency (kHz)

Photo 108-4

BW - 3KHz

Scan width - 100 KHz/div

Scan time - 0.1 sec/div

Figure 4-3. High Frequency Spectra of Pressure Signal.




Photo 108-5  
1 KHz Range  
+10 db Reference




Photo 108-6  
100 KHz Range  
-20 db Reference

Figure 4-4. Low Frequency Spectra of Pressure Signal.

Following the frequency spectra measurements, electrical calibration was performed on the CF-1-PT4 readout module by a TMI technician. No significant adjustments were noted during this calibration. After electrical calibration, power was removed from CF-1-PT4. The test fixture was removed and all signal lines between cable IT1722I and cabinet 156 were disconnected.

A series of active measurements (i.e., actively introducing a test signal into the circuit) was then performed. Table 4-1 shows the results of capacitance, impedance, and DC resistance measurements on the field cable lines. A set of TDR measurements was taken on the signal lines to determine possible cable defects. The resulting TDR traces are shown in Figures 4-5 to 4-7.



Table 4-1


## CAPACITANCE, IMPEDANCE, AND RESISTANCE MEASUREMENTS

| Signal             | Capacitance (nF) |      |        | Impedance (ohms) |      |        | Resistance      |
|--------------------|------------------|------|--------|------------------|------|--------|-----------------|
|                    | 100Hz            | 1kHz | 100kHz | 100Hz            | 1kHz | 100kHz |                 |
| +Signal<br>-Signal | 4                | 3.4  | 35     | 0F               | 0F   | 48     | 0F <sup>†</sup> |
| +Signal<br>Shield  | -- <sup>*</sup>  | 20   | 32     | 0F               | 0F   | 49     | 0F              |
| -Signal<br>Shield  | --               | 18   | 34     | --               | 6K   | 44     | 0F              |

\* Indicates data was erratic.

<sup>†</sup> Indicates overflow, i.e., above  $20 \times 10^6$  ohms.

STRIP CHART 108-1



Setting - 500 $\mu$ p/div

Range - 52.6 ft/div


Sensitivity - 0.25

Filter - 5 Hz

Cable dielectric - other

Figure 4-5. TDR Trace of Pressure Signal Lines.

STRIP CHART 108-2

Setting - 500 $\mu$ p/div

Range - 52.6 ft/div


Sensitivity - 0.25

Filter - 5 Hz

Cable dielectric - other

Figure 4-6. TDR Trace of (+) Signal to Shield.

STRIP CHART 108-3



Setting - 500 $\mu$ p/div

Range - 52.6 ft/div

Sensitivity - 0.25

Filter - 5 Hz

Cable dielectric - other

Figure 4-7. TDR Trace of (-) Signal to Shield.

## Section 5

### INTERPRETATION OF MEASUREMENTS

This section presents a summary of the interpretation of the measurements taken on CF-1-PT4. This interpretation is intended to indicate the condition of the device based on observed data.

Since this device varies from 10-40 ma for a 750 psi pressure range, the observation of 170 psi readout indicates that the current should be 19.07 ma. The measured current of 19.1 ma (1.91 volts across 100 ohms) matches within 1% of this expected value, which indicates the readout meter is correctly calibrated.

The time traces and frequency spectra do not indicate any serious contamination which would affect the DC readout. Table 5-1 lists the AC components present on the pressure signal. Note that even though up to 2.5 ma P-P fluctuations are present, readout devices normally respond at low frequencies. As a result, the worst-case effect of these AC variations is likely to be less than the 0.34 ma RMS value given for the 60 Hz components. Even with this relatively low value, this is an excessive noise level (approximately 1% of instrument range) and indicates a possible ground-loop problem.

The capacitance, impedance, and resistance data given in Table 4-1 is difficult to quantitatively interpret, but qualitative results are possible. The data indicates very low effective capacitance values, which would be expected from the amplifier section of the current loop driver. Other characteristics expected from the amplifier are extremely

5-2

Table 5-1

MAJOR AC COMPONENTS ON THE PRESSURE SIGNAL

| Frequency              | Amplitude                |
|------------------------|--------------------------|
| 60 Hz and harmonics    | 34 mV RMS (0.34 ma RMS)  |
| 16 kHz                 | 150 mV P-P (1.5 ma P-P)  |
| 16 kHz and harmonics   | 33 mV RMS (0.33 ma RMS)  |
| 160 kHz<br>(broadband) | <1 mV RMS (<0.01 ma RMS) |
| Total Spectrum         | 250 mV P-P (2.5 ma P-P)  |

high DC resistance values and decreasing impedance at higher frequencies. Since all expected phenomena are present, there is no obvious indication of instrumentation degradation from these measurements.

The results of TDR measurements performed on the cable (shown in Figures 4-5 to 4-7) are summarized in Table 5-2. Note that the lengths identified in the table are only approximate since no calibration of the cable resistance or insulation type was performed on the TDR instrument. As in other measurements, no indication of cabling problems is present in this data.

Table 5-2

## SUMMARY OF TDR MEASUREMENTS

| Signal Lines       | Distance* (ft) | Description**               | Probable Cause   |
|--------------------|----------------|-----------------------------|------------------|
| +Signal<br>-Signal | 189            | Point R increase            | Penetration R607 |
|                    | 505            | Large R increase            | Electronics      |
| +Signal<br>Shield  | 37             | Small continuous R increase | (?)              |
|                    | 200            | Point R increase            | Penetration R607 |
|                    | 411-474        | Point R small increase      | (?)              |
|                    | 510            | Large R increase            | Electronics      |
|                    | 32             | Small continuous R increase | (?)              |
| -Signal<br>Shield  | 200            | Point R increase            | Penetration R607 |
|                    | 411-474        | Point R small increase      | (?)              |
|                    | 511            | Large R increase            | Electronics      |

Note: Distances are not calibrated due to lack of prior information on the cable type which prevented calibration tests.

\* TDR to terminal block test cable (15 ft) not included in distance.

\*\* R is the abbreviation for resistance.

† Interpretation is difficult due to noisy signal.



## Section 6

### CONCLUSIONS

Based on the measurements, data reduction, and circuit analysis of CF-1-PT4, there is no indication of degradation of the instrument. The only abnormal contamination present in the pressure signal was the 16 kHz component. However, the amplitude of this signal was relatively low and, from other measurements performed at TMI, such a low-level 16 kHz component appears to be present on several unrelated instrument lines. Thus, this component is probably due to some common cause throughout the plant and is not a problem as long as the readout device properly discriminates against such high frequencies. In addition, the readout of another pressure monitor (CF-1-PT3) was noted to agree with the reading taken from CF-1-PT4. Checking the transmitter current output also produced the same current indication. Therefore, it appears that CF-1-PT3 is operational and probably calibrated since an independent monitor is producing the same output. However, there is a significant amount of 60 Hz ground loop noise present on the pressure signal which should be investigated.

APPENDIX

ORIGINAL FIELD PROCEDURES AND  
DATA SHEETS FOR CF-1-PT4

208-12

## UNIT 2

Page A-1

**RECOMMENDED  
PRIORITY**

CAUSE OF  
MALFUNCTION  
(IF KNOWN)

|                         |   |   |   |   |
|-------------------------|---|---|---|---|
| ORIGINATOR'S<br>EMP NO. |   |   |   |   |
| 0                       | 6 | 1 | 7 | 5 |

|                          |   |   |   |   |
|--------------------------|---|---|---|---|
| SUPERVISOR'S<br>EMP. NO. |   |   |   |   |
| 0                        | 4 | 1 | 7 | 5 |

|                   |   |   |   |   |        |   |   |   |  |
|-------------------|---|---|---|---|--------|---|---|---|--|
| WORK ORDER NUMBER |   |   |   |   |        |   |   |   |  |
| LOCATION          |   |   |   |   | SERIAL |   |   |   |  |
| 0                 | 3 | 6 | 0 | 0 | 0      | 1 | 8 | 7 |  |

|            |                   |
|------------|-------------------|
| GC<br>CODE | ACCOUNT<br>NUMBER |
| ▼          | ▼ X0001           |
| BD         | 787/019           |

| PLANT CONDITION |    |    |    |    |  |    |    |  |  |
|-----------------|----|----|----|----|--|----|----|--|--|
| SU              | OP | HD | CD | RF |  | HS | LR |  |  |
| /               | /  | /  | /  | /  |  | /  | /  |  |  |

| NPRD FAILURE |    |     | START |     |
|--------------|----|-----|-------|-----|
| YR           | MO | DAY | HR    | MIN |
|              |    |     |       |     |

|                     |   |               |   |                       |                   |
|---------------------|---|---------------|---|-----------------------|-------------------|
| TRANS<br>MUC<br>REQ | W | MUC<br>SAFETY | W | REG<br>AGENCY<br>CODE | CHG/MOD<br>NUMBER |
| 0                   | 0 | 0             | 0 |                       |                   |

|             |                         |  |  |  |  |
|-------------|-------------------------|--|--|--|--|
| ENV<br>CODE | OUTAGE<br>CAUSE<br>CODE |  |  |  |  |
| X           |                         |  |  |  |  |

|        |  |
|--------|--|
| STATUS |  |
| HOLD   |  |
| CODE   |  |

|               |     |    |  |  |
|---------------|-----|----|--|--|
| S M APPROVAL  |     |    |  |  |
| COMMENCE WORK |     |    |  |  |
| MO            | DAY | YR |  |  |
| 09            | 23  | 80 |  |  |

|                       |                                |   |   |   |
|-----------------------|--------------------------------|---|---|---|
| P<br>R<br>I<br>V<br>E | RESP LOCATION<br>OR CONTRACTOR |   |   |   |
|                       | ▼                              |   |   |   |
|                       | 2                              | 0 | 3 | 6 |
|                       |                                |   |   |   |

Location Cable Road, 305' elevation Control Bulky

Comply with the Provisions  
set forth in AP 1002 and

**a) Personnel**

### c) Environment

**ENSURE WORK AREA CLEANED**

Post Maintenance Testing required and Acceptance Criteria **AT COMPLETION OF JOB**

**STOP AT COMPLETION OF JOB**

**JOB TICKET (WORK REQUEST)**  
**REVIEW - CLASSII**      **NG CONTROL FORM**  
Page A-2

JOB TICKET NUMBER C5714

1. Does work represent a change or modification to an existing system or component? If yes, an approved change modification is required per AP 1021.

C/M No. NA

Yes \_\_\_\_\_ No ✓

- 2a. Does work requires an RWP?

Yes \_\_\_\_\_ No ✓

- 2b. Is an approved procedure required to minimize personnel exposure?

Yes \_\_\_\_\_ No ✓

- 3a. Is work on a QC component as defined in GP 1008?

Yes \_\_\_\_\_ No ✓

- 3b. If 3a is yes does work have an effect on Nuclear Safety? If 3b is yes, PORC reviewed Superintendent approved procedure must be used.

Yes \_\_\_\_\_ No ✓

4. Agreement that a PORC reviewed, Superintendent approved procedure is not required for this work because it has no effect on nuclear safety. (Applies only if 3a is Yes and 3b is No).

NA  
UNIT SUPERINTENDENT

DATE

- 5a. Is the system on the Environmental Impact list in AP 1026?

Yes \_\_\_\_\_ No ✓

- 5b. If 5a is YES, is an approved procedure required to limit environmental impact?

Yes \_\_\_\_\_ No ✓

6. Agreement that 5b is No. (Required only if 5a is Yes).

NA  
UNIT SUPT / SUPV OF OPERATIONS

DATE

7. Plant status or prerequisite conditions required for work. (Operating and/or shutdown)

8. QC Dept. review, if required in item No. 3.

NA  
QC SUPERVISOR

DATE

9. Does work require code inspector to be notified?

Yes \_\_\_\_\_ No ✓

10. Supervisor of Maintenance approval to commence work:

Date 9/23/80

11. Maintenance Foreman Assigned J. R. Gilbert

12. Code Inspector Notified. Name \_\_\_\_\_

Date \_\_\_\_\_

13. Shift Foreman's approval to commence work. [Signature]

Date 9/23/80

Initial if Shift Foreman signature is not required

WORK REQUEST PROCEDURE  
TMI Nuclear Station  
Maintenance      Page A-3      and Approval

Unit No. 2

This form outlines the format and acts as a cover sheet for a maintenance procedure. Due to the limited size of the form, additional pages may be attached as required. Work Request procedure AP 1016 Section 6 should be used as a guide in preparing the maintenance procedure.

1. Procedure Title & No.:

*Sensor / Cable measurements for CF-1-PT4  
Core Flood Tank B Pressure.*

2. Purpose:

*To determine signal characteristics of sensor/cable as it  
exists in Reactor Building.*

3. Description of system or component to be worked on.

*CF-1-PT4*

4. References:

*See attached*

5. Special Tools, and Materials required.

*See attached.*

6. Detailed Procedure (attach additional pages as required)

*See attached*

Supervisor of Maintenance recommends approval

Date

*9/23/80  
9/22/80*

• PORC RECOMMENDS APPROVAL

Unit No. 1 Chairman

Date

Unit No. 2 Chairman

Date

• UNIT SUPERINTENDENT APPROVAL

Unit No. 1

Date

Unit No. 2


Date

• Standing Procedure

Supervisor of QC

Date

\*Note: These approvals required only on Nuclear Safety Related/Radiation work permit jobs.

|  |  |                                    |
|--|--|------------------------------------|
| <br>Technology for Energy Corporation | <b>TITLE</b> IN-SITU MEASUREMENTS OF CABLES AND<br>SIGNALS FROM CORE FLOOD TANK B<br>PRESSURE CF-1-PT4 | <b>NO.</b> TP-108<br><b>REV.</b> 0 |
|  | Page A-4<br><b>APPROVED</b><br>M.V. Mathis, Director, Tech. Serv. Div.                                 | <b>DATE</b><br>9-16-80             |
| <b>PROCEDURE</b>   |  |                                    |

PURPOSE: The purpose of these measurements is to gather baseline data and information in preparation for removal of the Force Balance Transmitter CF-1-PT4 from the Reactor Building TMI Unit 2. The tests specified in this procedure are designed to assess the condition of the in-containment transmitter associated cabling, and readout devices. This assessment will require the use of Time Domain Reflectometry (TDR), Impedance (Z), Spectral Analysis (frequency domain), and general oscilloscope observations (with recording) of waveforms from/to the unit under test (UUT). *Core Flood Tank Pressure*

PROCEDURE (ADMINISTRATIVE):

A. Limitations and Precautions

1. Nuclear Safety. The unit is <sup>not</sup> part of the engineered reactor safeguards system and is nuclear safety-related. *Core Flood Tank B Pressure*
2. Environmental Safety. Force Balance Transmitter CF-1-PT4 can be taken out-of and restored to services without producing a hazard to the environment.
3. Personnel Safety. The test described herein produces no additional personnel safety hazards other than normally associated with performing instrument testing.
4. Equipment Protection. In the performance of each test described herein, care will be taken to insure adequate equipment protection as follows:
  - a. In all cases actual test hookups to the Unit-2 instrumentation shall be made and verified by Instrumentation Personnel.
  - b. All passive measurements (Spectral Analysis and Oscilloscope observations) of waveforms and signals from powered instruments shall be performed using high input impedance probes or inputs ( $Z = \geq 1$  Meg ohm) to prevent loading of signals.
  - c. In all Time Domain Reflectometry and Impedance measurements, power will be removed from the unit under test and low level test signals prescribed in Table 4-1 shall be utilized to perform cable integrity measurements on the appropriate instrumentation cables by inserting test signals on appropriate conductors of Cable IT1722I. Terminations shall be removed and replaced on TB 8-9-3 of Cabinet 156.

Table 4-1 Active Measurements

| Active Signal Parameter | Time Domain Reflectometry         | Impedance                     |
|-------------------------|-----------------------------------|-------------------------------|
| Voltage                 | 225 mV nominal (into 50 ohm base) | $\leq 5V$ rms                 |
| Frequency               | ---                               | 100Hz, 1kHz,<br>10kHz, 100kHz |
| Current                 | $\leq 10mA$                       | $\leq 100mA$                  |
| Other                   | 225mV, 110 picosecond pulses      | ---                           |

- d. In the calibration verification measurements section, baseline data on the as-found condition will be recorded prior to the performance of any adjustments or electronic calibrations.

B. Prerequisites

1. The Shift Supervisor/Shift Foreman shall be notified for concurrence prior to the performance of those measurements.
2. Instrumentation personnel shall be assigned to assist in the performance of these measurements.
3. All measurements and test instrumentation shall be in current calibration (traceable to NBS).
4. The Shift Supervisor/Shift Foreman shall be notified prior to starting and upon completion of the measurements.

C. Procedure for Performing Measurements

References:

1. Burns & Roe Dwg. 3024, Sh. 20.
2. Service Manual for Foxboro Series E10 Force-Balance Transmitter.
3. Burns & Roe Dwg. 3304, Sh. 24.
4. Burns & Roe Dwg. I.C. 3343, Sh. 4.

TEC

TITLE

IN-SITU MEASUREMENTS OF CABLES AND SIGNALS  
FROM CORE FLOOD TANK PRESSURE CF-1-PT4

NC. TP-108

REV. 0

Page A-6

5. Burns & Roe Dwg. 3343, Sh. 4.
6. Burns & Roe Dwg. 3304, Sh. 26.
7. Burns & Roe Dwg. 3304, Sh. 23.
8. Burns & Roe Dwg. 3024, Sh. 20.
9. Instruction Manual, Tektronix Model 1502 Time Domain Reflectometer.
10. Instruction Manual, Hewlett Packard Model 4274 Multifrequency LCR Meter.
11. Instruction Manual, Hewlett Packard Spectrum Analyzer (Model 141T, 8553B, 8552B Modules).
12. Instruction Manual, Nicolet Model 444A-26 Spectrum Analyzer.
13. Instruction Manual, Tektronix Model 335 Oscilloscope.
14. Instruction Manual, Lockheed Store-4 Recorder.
15. Instruction Manual, Tektronix SC502 Oscilloscope.
16. TEC Composite Electrical Connection Diagram, CF-1-PT4 (see attachment).

| SIGNAL | CABLE   | CABINET<br>156        |
|--------|---------|-----------------------|
| + Sig  | IT1722I | TB <del>D</del> 9-3/4 |
| - Sig  | IT1722I | TB <del>B</del> 9-3/5 |
| SHLD   | IT1722I | TB <del>B</del> 9-3/3 |

#### STEPS

1. Notify Shift Supervisor/Shift Foreman of start of test on CF-1-PT4.
2. Verify power is applied to CF-1-PT4.
3. Record present reading from CF-1-PT4 Readout Module.



TEC

TITLE

IN-SITU MEASUREMENTS OF CABLES AND SIGNALS  
FROM CORE FLOOD TANK PRESSURE CF-1-PT4

NC. TP-108

REV. 0

Page A-7

| SIGNAL              | READING IN PSI |
|---------------------|----------------|
| CF-1-PT4<br>Readout | 170            |

4. Remove all power from CF-1-PT4.

*Q. TS* 9/25/80  
Signature/Date


5. <sup>Locate</sup> ~~Open link~~ TB 8-9-3/4 in Cabinet 156.

*Q. TS* 9/25/80  
Signature/Date

6. Insert TEC test fixture (100 ohm, 1.0% resistor) <sup>across terminals</sup> ~~across open link~~ TB 8-9-3/4 per Figure 6-1 to convert 10-50 mA signal to voltage.

Cabinet 156  
To TB 8-9-3/4 5  
Cabinet Side  
FLOOR  
  
To TB 8-9-3/4 5  
Back Side  
CABINET

FIGURE 6-1.



NOTE: This circuit converts the 10-50 ma signal to 1-5 V for testing.

TEC

TITLE

IN-SITU MEASUREMENTS OF CABLES AND SIGNALS  
FROM CORE FLOOD TANK PRESSURE CF-1-PT4NC.  
TP-108

REV. 0

Page A-8

7. Apply power to CF-1-PT4 and wait 10 minutes for instrument warm-up.
8. Record present reading from CF-1-PT4 Readout Module.

| SIGNAL              | READING IN PSI |
|---------------------|----------------|
| CF-1-PT4<br>Readout | 170 PSI        |

9. Connect\* differential Conditioning Amplifier (TEC Model 901) to the Force Balance Transmitter (TB 8-9-3/4; in Cabinet 156). Connect Model 901 output to FM Recorder and record Signal for 30 minutes. Remove recorder when completed.

\*NOTE: Connection across banana jacks 1&2 of current-to-voltage test fixture (see Step 6).

10. Using a Keithley Model 177 DMM (or equivalent, Range 0-2000 V, Precision  $\pm 1\%$ ) measure the DC Voltage or current at the following test point.

| <u>SIGNAL</u> | <u>CABINET 156</u>       | <u>TEST LEAD</u> | <u>READING</u>          |
|---------------|--------------------------|------------------|-------------------------|
| *a.           | TB 8-9-3/4<br>TB 8-9-3/4 | (+)<br>(-)       | Signal <u>1.905 VDC</u> |

\*Across test fixture banana jacks 1&2 (see Step 6).

*Q. T. S. A. 9/25/80*  
Signature/Date

11. Using a Tektronix Model SC502 (or equivalent) oscilloscope observe the waveform at the following test point:

**TEC**

**TITLE**

IN-SITU MEASUREMENTS OF CABLES AND SIGNALS  
FROM CORE FLOOD TANK PRESSURE CF-1-PT4

NO. TP-108


REV. 0

Page A-9

| <u>SIGNAL</u> | <u>CABINET 156</u>                             | <u>PARAMETER</u> |   |  |   |
|---------------|--|------------------|---|--|---|
| *a.           | TB <del>8</del> 9-3/4<br>TB <del>8</del> 9-3/4 | SIG              | Photo <u>10B-1</u><br>Time Base <u>2ms</u><br>Vert Gain <u>50mV</u> | Photo <u>10B-2</u><br>Time Base <u>50ms</u><br>Vert Gain <u>50mV</u> | Photo _____<br>Time Base _____<br>Vert Gain _____ |

\*Across test fixture banana jacks 1&2 (see Step 6).

Sync the oscilloscope and photograph the waveform using up to three time base and vertical gain settings. Mark the back of the photographs with the instrument tag number and parameter measured.

  
Signature/Date

12. Using a Hewlett-Packard Spectrum Analyzer (Models 141T, 8553B and 8552 or equivalent) perform an analysis of the following signal for spectral content:

| <u>SIGNAL</u> | <u>CABINET 156</u>                             | <u>PARAMETER</u> | <u>PHOTO #</u>              |
|---------------|--|------------------|-----------------------------|
| *a.           | TB <del>8</del> 9-3/4<br>TB <del>8</del> 9-3/4 | SIGNAL           | <u>08-3</u><br><u>10B-4</u> |

\*Across test fixture banana jacks 1&2 (see Step 6).

Before photographing each scope display adjust analyzer for best spectral resolution. Record critical analyzer parameters e.g., RF bandwidth, RF bandwidth and sweep speed on rear of photograph as well as parameter analyzed.

# TEC

TITLE

IN-SITU MEASUREMENTS OF CABLES AND SIGNALS  
FROM CORE FLOOD TANK PRESSURE CF-1-PT4

NO. TP-108

REV. 0

Page A-10

SPECTRUM IDENT    FREQUENCY    AMPLITUDE    REMARKS

BANDWIDTH    SCAN WIDTH    INPUT RTEN    SCAN TIME    LOG REF    GEN    PWR

3KHz    1MEG Hz / DIV    0    1 SEC    -20db    0    108-3

3KHz    0.1 MEG Hz / DIV    0    0.1 SEC    -20db    0    108-4

*Q. T. S. A* 9/25/80  
Signature/Date

13. Using the Nicolet Model 444 FFT Analyzer (or equivalent) perform FFT analysis of signals for the following test point:

| <u>SIGNAL</u> | <u>CABINET 156</u>       | <u>PARAMETER</u> | <u>PHOTO #</u> |
|---------------|--------------------------|------------------|----------------|
| *a.           | TB 8-9-3/4<br>TB 8-9-3/4 | SIGNAL           | 108-5<br>106-6 |

\*Across test fixture banana jacks 1&2 (see Step 6).

*Q. T. S. A* 9/25/80  
Signature/Date

TEL

TITLE

IN-SITU MEASUREMENTS OF CABLES AND SIGNALS  
FROM CORE FLOOD TANK PRESSURE CF-1-PT4

NC. TP-108

REV. 0

Page A-11

14. Inside Cabinet 156 perform usual electronic calibrations using applicable instrument shop procedures. Attach instrument shop calibration data sheet and record any significant adjustments or problems in the space below.

| Procedure Step                                     | Remarks |
|--|---------|
|  |         |
| See attached instrument shop procedure data sheet. |         |

Instrument Shop Procedure No. \_\_\_\_\_

Signature/Date \_\_\_\_\_

15. Remove all power from CF-1-PT4.

*Q. T. S. H. 9/25/80*  
Signature/Date

16. Open links for field wires from Cable IT1722I at TB 8-9-3/3, 4, and 5 (Cabinet 156) and remove test fixture (installed in Step 6).

| <u>TERMINAL</u>        | <u>SIGNAL IDENT.</u> |
|------------------------|----------------------|
| TB <del>8</del> -9-3/4 | (+) SIGNAL           |
| TB <del>8</del> -9-3/5 | (-) SIGNAL           |
| TB <del>8</del> -9-3/3 | SHIELD               |

Signature/Date \_\_\_\_\_

TEC

TITLE

IN-SITU MEASUREMENTS OF CABLES AND SIGNALS  
FROM CORE FLOOD TANK PRESSURE CF-1-PT4

NO. TP-108

REV. 0

Page A-12

17. Using the Hewlett-Packard Model 4274 (or equivalent) Impedance Bridge, measure the capacitance and impedance at the following test points:

| TEST POINT | FROM              | TO               |
|------------|-------------------|------------------|
| a.         | 8-9-3/4 (+SIG)    | TB 9-3/5 (- Sig) |
| b.         | TB-8-9-3/4 (+SIG) | TB 9-3/3 (SHLD)  |
| c.         | TB-8-9-3/5 (-SIG) | TB 9-3/3 (SHLD)  |

Record the data required below:

| Test Point      | Capacitance |        |         | Impedance |       |            |
|-----------------|-------------|--------|---------|-----------|-------|------------|
| Frequency       | 100 Hz      | 1 kHz  | 100 kHz | 100 Hz    | 1 kHz | 100 kHz    |
| a. TB 9-3/4:5   | 4 nF        | 3.4 nF | 35 nF   | OF        | OF    | 485 / -107 |
| b. TB 9-3/4:3   | ~           | 22 nF  | 35 nF   | OF        | OF    | 455 / -850 |
| c. TB 8-9-3/5:3 | ~           | 20 nF  | 32 nF   | OF        | OF    | 445 / -86  |

*J. T. S.* 9/25/86  
Signature/Date

18. Using the Tektronix Model 1502 (or equivalent) TDR unit perform TDR measurements on three test points and record the data below.

TEL

TITLE

IN-SITU MEASUREMENTS OF CABLES AND SIGNALS  
FROM CORE FLOOD TANK PRESSURE CF-1-PT4

NO. TP-108

REV. 0

Page A-13

| Test Point                                | Instrument Settings | Strip Chart Number |
|---|---------------------|--------------------|
|   | Ampl Range Mult     |                    |
| a. TB <del>8</del> 9-3/4:5 (+ Sig: - Sig) |                     | <del>108-1</del>   |
| b. TB <del>8</del> 9-3/4:3 (+ Sig: SHLD)  |                     | 108-2              |
| c. TB <del>8</del> 9-3/5:3 (- Sig: SHLD)  |                     | 108-3              |

*[Signature]* 9/25/80  
Signature/Date

19. Using the Keithley Model 144 (or equivalent DMM) perform resistance measurements on the test points specified and record values in the space provided.

|            |                       |                       | POLARITY<br>From = +; To = - | POLARITY<br>From = -; To = + |
|------------|-----------------------|-----------------------|------------------------------|------------------------------|
| TEST POINT | FROM LINK             | TO LINK               | RESISTANCE                   | RESISTANCE                   |
| a.         | TB <del>8</del> 9-3/4 | TB <del>8</del> 9-3/5 | OPEN                         | OPEN                         |
| b.         | 8-9-3/4               | TB <del>8</del> 9-3/3 | OPEN                         | OPEN                         |
| c.         | 8-9-3/5               | TB <del>8</del> 9-3/3 | OPEN                         | OPEN                         |

*[Signature]* 9/25/80  
Signature/Date

TEC

TITLE

IN-SITU MEASUREMENTS OF CABLES AND SIGNALS  
FROM CORE FLOOD TANK PRESSURE CF-1-PT4

NO. TP-108

REV. 0

Page A-14

20. Close links for field wires from Cable IT1722I at TB 8-9-3, 4, and 5  
(Cabinet 156) and restore power.

21. Notify the Shift Supervisor/Shift Foreman of the conclusion of testing NI-AMP-2.

I hereby certify that this Test Procedure has been completed as written and that  
all data has been correctly entered and filed as requested.

TEC Representative

*[Signature]* 9/25/80  
Signature/Date

Instrumentation

*[Signature]*  
Signature/Date



## Page A-15

TMI 199 580